

Addendum #1

June 22, 2026

Lindsay Wellness Center

Pool Deck Renovation Project

Bid Walk comments and questions:

- Temporarily remove the artificial turf, then recompact soil before re-installing the turf. Demolition drawing X-001 has been revised to reflect added scope of work.
- Demolition drawing will be revised to include note “Demo existing water feature”. Demolition drawing X-001 has been revised to reflect added scope of work.
- Please Include a separate line item for all new handrails, but do not remove the cost for polishing and refurbishing existing handrails from your bid. Dimensions for the handrails have been added to sheet L-003.
- Cover abandoned wall plates. Demolition drawing X-001 has been revised to reflect added scope of work.
- 10pm – 7am Noise Restriction. Sheet G-001 has been revised to include this in the scope of work.
- Pool concrete demolition boundary will be moved to nearest expansion joint. Plans and square footage will be revised and resubmitted. Demolition drawing X-001 has been revised to reflect the new square footage.
- City of Lindsay will be doing the inspections. City of Lindsay requires a certified welder for the scoreboard.
- Special Inspections: City of Lindsay requires a minimum relative soil compaction of **95 percent** for both the subgrade and the aggregate base material. Sheet G-001 has been revised to include this special inspection.

Questions submitted after Bid Walk:

Q: Does the scoreboard need an on/off button?

A: Currently, we use a breaker in the breaker box to turn on and off.

Q: Is there a specific color for the scoreboard?

A: Black

I acknowledge receipt of Addendum #1 as described above:

Signature: Armando M. da Silva

Printed Name: Armando M. da Silva

Company: City of Lindsay

Date: 06/22/2026